

NAIONAL INSTITUTE OF TECHNOLOGY, TIRUCHIRAPPALLI - 620015

DEPARTMENT OF ESTATE MAINTRNANCE

SCHDULE OF WORKS

Name of Work : C/o Compound wall around ADM Block (Civil Works)

Agency :

Ref : NITT/CoW/EMD/Civil Works/ Eq.No.60(66)/14-15 ,dt.29.05.2014 Due on 10.06.2014 @ 3.00 p.m

ITEM No	SUB-HEADS AND ITEM OF WORK	QUANTITY	UNIT	RATE (Rs)	RATE (In Words)	AMOUNT(Rs)
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30cm in depth. 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50m and lift upto 1.5m, disposed earth to be levelled and neatly dressed.	110.00	cum			
1.1	All kinds of soil					
2	Supplying and filling in plinth with river sand under floors, including watering, ramming, consolidating and dressing complete.	31.00	cum			
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :	31.00	cum			
3.1	1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size)					
4	Brick work with common burnt clay modular bricks of class designation 3.5 in foundation and plinth in:	57.00	cum			
4.1	Cement Mortar 1:6 (1 cement : 6 coarse sand).					
5	12 mm cement plaster of mix :	610.00	sqm			
5.1	1:6 (1 cement: 6 fine sand)					

ITEM No	SUB-HEADS AND ITEM OF WORK	QUANTITY	UNIT	RATE (Rs)	RATE (In Words)	AMOUNT(Rs)
6	Finishing walls with Acrylic Smooth exterior paint of required shade :					
6.1	New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	610.00	sqm			
7.1	With water thinnable cement primer on wall surface having VOC content less than 50 grams/litre	610.00	sqm			
8	Dismantling barbed wire or flexible wire rope in fencing including making rolls and stacking within 50 metres lead.	200.00	kg			
9	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	9.00	cum			
10	Brick work with common burnt clay modular bricks of class designation 3.5 in superstructure above plinth level up to floor V level in all shapes and sizes in Cement Mortar 1:6	34.00	Cum			

Signature of Contractor

Sd-
Chief of Works